

SURVEY & REMONUMENTATION COMMISSION
 APR 10 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 89

For corners of
St. Joseph
 (County)

Located In:

Corner Code #

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

20 DEC 94 12:40 P.M.

CYNTHIA JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 8 S R 10 W. C-2
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
- S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald C. Andrews, in a field survey on November 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Post, LCRC 3, P 154 Mostrom in 1976 set corner midway. pipe/box Co. Rd. records show corner was dug for and not found Sayers survey in 1976 shows corner set midway and on line with adjacent section corners

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

found record pipe in box and checks with distance to house. Remonumentation Peer group determined that corner is good even if one of the locations of the section corners were in the exact location.

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON Nov. 14, 19 94
Michigan CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Reset Remon. capped iron where pipe was.

- 1) 36" oak West 36.81'
- 2) fence post S44°W 46.03'
- 3) SE corner house N68°W 71.70'
- 4) 30" oak N32°E 68.40'
- 5) NE corner porch N42°W 90.65'



LIBER 4 PAGE 89

Signed by Donald C. Andrews

Date 12-12-94

Surveyor's Michigan License No. 33967

REMONUMENTATION