

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>St. Joseph</u> (County)	Located In:	Corner Code #
Sturgis Township 1. Public Land Survey	T8S R 10W	C-4
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

LIBER 5 PAGE 157

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

27 APR 1999 1:21:26 PM

CYNTHIA L. JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Wayne A. Mostrom, in a field survey on March 23, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7	8			9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Mostrom 1980 Survey
 3/4" Pipe in Mon. Box
 in centerline existing pavement
 Cedar Post=East 32'
 P.P.=S23°E 71'

A. Description of original monument and accessories and/or subsequent restoration:

<u>1865 Survey in A/112</u> Stone 1/2 way between corners	<u>Road Comm. - 1964</u> Large Pointed Stone In Mon. Box Fence to East = North 338.3' A.P.=S88°E 31.8' Nail in P.P.=S23°E 71.30'	<u>Sayers 1982 Survey</u> Pipe in Mon. Box Fence Post=East 32.4" P.P.=S7.5°E 70.8' PK Nail on section line-South 30'	<u>1989 LCRC in 2/228</u> 3/4" Pipe in Mon. Box in centerline N-S Roadway A.P.=East 32.06' P.P.=S26°E 68.95' GTE Jct. Box (Center) = N29°W 61.9'
--	--	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 12" pipe over stone 16" deep In Mon. Box
 in centerline N-S Pavement
 A.P. = S88°E 31.8'
 Fence Post = East 32.4'
 All witness's are in OK. per 1989 LCRC

**RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON APRIL 19, 1999
 CO. REPRESENTATIVE**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 14" bar w/std. cap in
 conc. over stone In Mon. box
 N & W in SW side P.P. = S26°E 68.95'
 N & W In E. side 12" Elm = N26°E 82.33'
 Set 1" x 18" Iron bar = East 16.00'
 Set 1" x 18" Iron bar = West 16.00'



Signed by Wayne A. Mostrom Wayne A. Mostrom Date March 25, 1999
 Surveyor's Michigan License No. 14100

REMONUMENTATION

LIBER 5 PAGE 157