

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|-------------------|---------------|
| <u>St. Joseph</u> (County) | Located in: | Corner Code # |
| 1. Public Land Survey | T 8S R 10W | C-5 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

LIBER 5 PAGE 158

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

27 APR 1999 1:21:53 PM

CYNTHIA L. JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Wayne A. Mostrom, in a field survey on Mar. 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|--|--|--|
| <u>1865 Survey in A/110 & A/112</u> Stk. & sto. set from old brg's 8" Butternut=N46°E 70½ lks (46.53') 4" W.O.=S21°W 1.275 chs (84.15') | <u>Road Comm. - 1960's</u> Large sto. under Mon. box (Pg. 52 in field notes) | <u>Mostrom 1988 Survey</u> Fd. sto in Mon box P.K. in P.P. = SE 37' SE cor. slab = NW 52.28' Cor. is 0.5' S of ζ asphalt |
| <u>1875 Survey in A/256</u> Same as above | <u>Sayers 1964 Survey</u> Shows "Mon. box" | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found large stone w/rounded top & chiseled "+" in Mon. box in ζ - ζ of paved roads
 SE cor. slab = NW 52.28'

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON APRIL 19, 1999
Wayne CO, REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" X 6" bar w/std. cap in concrete over +'d stone in Mon. Box
 N & W in SW side P.P. = S39°E 39.0'
 N & W in W side P.P. = S15°E 204.75'
 N & W in N side P.P. = S75°W 168.13'
 N & W in E Utility Pole = N15°W 144.7'



LIBER 5 PAGE 158

Signed by Wayne A. Mostrom
 Surveyor's Michigan License No. 14100

Date 4/28/99

REMONUMENTATION