

SURVEY & LAND CORNER RECORDATION CERTIFICATE
 REMONUMENTATION Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 80

For corners in

St. Joseph (County)

Located In:

Corner Code #:

APR 10 1995

COMMISSIONER

- 1. Public Land Survey T 10 W D-3
 R _____
 T _____
 R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Séc. S _____ T _____ R _____

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

20 DEC 94 12:36 P.M.

CYNTHIA JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3			●										
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald C. Andrews, in a field survey on November 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO May 15 Post, Co. Surveyor Book B, P. 144, S. Reed May 1905 Stone set midway. 51k(3.30') North of N. rail, Co. Surveyor Book 1, P. 106, S. Reed large pointed stone(same as above) July 1905. LCRC 3, P 154 Mostrom found pointed stone as found by Sayers in 1968. Sayer's survey in 1970 and 1976 found pointed stone. Mostrom's survey 1980 found pointed stone 3.20' North of N. rail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found record stone

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON Nov. 14, 1994
Wm CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remon. capped iron where stone. 1) Twin Cherry North 43.03'
- was. Moved stone over to north 2) PK/Tag in RR tie S70°W 10.33'
- side of set standard remon capped 3) " " " S10°E 2.35'
- iron. 4) " " " East 6.97'



LIBER 4 PAGE 0V

Signed by Donald Andrews

Date 12-12-94

Surveyor's Michigan License No. 33967

REMONUMENTATION