

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 131

For corners in St. Joseph Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 8S R 10W E-1 _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED
 18 APR 95 2:11 P.M.
 CYNTHIA JARRATT
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, Donald C. Andrews, in a field survey on December 15, 1994, do hereby certify that under requirements of P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: GLO - 1825 Post W.Oak 30" N83° 0.76 ch & W.Oak 12" N25°W 3.74 ch
- 1877 - N.S. Andrews Stone from B.T. Yel. Oak 14" N51°E 0.875 ch W. Oak 12" N20°E 1.08 ch
- 1957 - Co. Road Com. - Records shows corner (no description or wit)
- 1975 - LCRC Pipe in box
- 1976 - LCRC 3, p. 154 Pipe in box
- 1976 - Sayers survey # 9842 Pipe/box

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5	4	3	2	1					
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON Dec. 12, 1994
Wam CO. REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Record 1/2" pipe x 9" over stone in box. wit. from LCRC 3, P. 154 check close stone ±10 inches below surface

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- set standard capped iron in concrete over stone
- Wit. RR rail S40°E 44.40'
- CONC. A.P. S45°W 45.50'
- TEL. POLE N44°E 43.40'
- 26" TREE S30°W 68.70'



LIBER 4 PAGE 131

Signed by Donald C. Andrews Date March 14, 1995
 Donald C. Andrews, P.S.

Surveyor's Michigan License No. 33967

REMONUMENTATION