

# SURVEY & REMONUMENTATION

APR 07 1998

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 5 PAGE 45

### SECTION

ST. JOSEPH <small>(County)</small>	Located In:	Corner Code #
WHITE PIGEON TWP. 1. Public Land Survey	T 8S R 11W	C-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

30 DEC 97 12:59 P.M.

CYNTHIA JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID W. MOSTROM, in a field survey on NOV. 26, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

#### A. Description of original monument and accessories and/or subsequent restoration:

- (C-4) 1/4 CORNER COMMON TO SECTIONS 7 & 8, T8S R11W
- \* 1974 SURVEY BY MOSTROM      \* 1976 LCRC IN BK 3, PG 158
- SET 6' LONG IRON BAR      SET 5/8" X 18" IRON BAR
- 4" TRIPLE LOCUST = NW 53.60'      4" TRIPLE LOCUST = NW 53.60'
- 18" POPLAR = WEST 282.81'      18" POPLAR = WEST 282.81'
- 4" LOCUST = SW 66.25'      4" LOCUST = SW 66.25'
- \* THIS CORNER HAS SINCE BEEN USED ON MANY SURVEYS IN SECTIONS 7 & 8 INCLUDING THE RECORDED PLATS OF LAKE WAHBE MEME ESTATES NO. 1, 2 & 3

#### B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- (C-4)
- FOUND 3/8" IRON BAR IN MARSH
- W. EDGE MARSH = WEST 280'±
- 12" TRIPLE LOCUST = N70°W 55.70'
- 12" DBL. LOCUST = S47°W 66.25'
- NO OCCUPATION IN ANY DIRECTION AT CORNER
- SET 5/8" X 48" IRON BAR W/STD. CAP IN PLACE OF 3/8" IRON FOUND

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON DEC. 8, 1997  
MICHIGAN CO. REPRESENTATIVE

#### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (C-4) 1/4 CORNER COMMON TO SECTIONS 7 & 8, T8S R11W
- 5/8" X 48" IRON BAR W/STD. CAP IN MARSH
- N & W IN NW SIDE OF 12" DBL. LOCUST = S47°W 66.25'
- N & W IN N. SIDE OF 12" TRIPLE LOCUST = N70°W 55.70'
- N & W IN N. SIDE OF 8" DBL. LOCUST = N45°W 50.80'
- CONC. MON. ON S. LINE OF LOT 17 OF LAKE WAHBE MEME EST. NO. 1 = N27°27'56"E 795.07'
- CONC. MON. ON S. LINE OF LOT 11 OF LAKE WAHBE MEME EST. NO. 1 = N70°43'27"E 905.60'

Signed by J. W. Mostrom      DAVID W. MOSTROM      Date DECEMBER 9, 1997  
Surveyor's Michigan License No. 32339



LIBER 5 PAGE 45