

**SURVEY & REMONUMENTATION**

JUL 16 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **5** PAGE **61**

For corners in

<u>ST. JOSEPH</u>	Located In:	Corner Code #
(County)		
<u>MOTTVILLE TWP.</u>		
1. Public Land Survey	T <u>8S</u> R <u>12W</u>	<u>I-4</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

STATE OF MICHIGAN  
ST. JOSEPH COUNTY  
FILED

15 Apr 1998 3:32:34 PM

CYNTHIA L. JARRATT  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, WAYNE A. MOSTROM, in a field survey on APRIL 14, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>GLO</u>	<u>1974 LCRC IN 3/169</u>	<u>1983 LCRC IN 2/168</u>	<u>1993 SURVEY</u>
16" W.O. = N52°E 28 LKS	1" PIPE OVER STO. FD.	½" IRON REROD	FD. ½" IRON OVER
12" W.O. = S48°W 27 LKS	17" SPRUCE = W. 38.25'	18" SPRUCE = N81°W 38.3'	PIPE
<u>ROAD COMM.</u>	NE COR. PORCH = SW 127.9'	30" MAPLE = S37°W 45.32'	E.P. = E. 8'
<u>LARGE STO. UNDER 1" PIPE</u>	34" CHERRY = E. 42.9'	P. POLE = N65°E 97.77'	36" MAPLE = S21°W
17" SPRUCE = N81°W 38.25'			85.55'
A.P. = N. 26.6', PORCH = S53°W 127.9'			40" MAPLE = S37°W
38" ELM = N36°E 41.55', 34" CHERRY = E. 42.9'			45.51'
<u>B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:</u>			NE COR. PORCH =
FD. ½" X 26" BAR DRIVEN INTO 1" X 13" PIPE OVER #1 D STONE 36" DEEP			S53°W 127.9'
17" SPRUCE = N81°W 38.25'			A.P. = S45°W 35.09'
A.P. = N. 26.6'			
NE COR. PORCH = S53°W 127.9'±			
18" SPRUCE = N81°W 38.8'			
30" MAPLE = S37°W 45.32'			
P.P. = N65°E 97.77'			
36" MAPLE = S21°W 85.55'			
A.P. = S45°W 35.09'			

RATIFIED BY PEER GROUP  
IN ACCORDANCE WITH P.A. 345  
ON April 14, 1998  
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 5/8" X 24" IRON BAR W/STD. CAP
- NE COR. PORCH FTDN. = S53°W 127.73'
- N & W IN N. SIDE 26" SPRUCE = N81°W 38.25'
- N & W IN E. SIDE A.P. = NORTH 34.85'
- N & W IN TOP OF A.P. = S45°W 27.12'
- N & W IN S. SIDE P. POLE = N65°E 97.77'
- N & W IN E. SIDE 36" MAPLE = S21°W 85.55'



LIBER **5** PAGE **61**

Signed by Wayne A. Mostrom WAYNE A. MOSTROM  
Surveyor's Michigan License No. 14100

Date APRIL 14, 1998