

SURVEY & REMONUMENTATION

JUL 16 1998

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 **LIBER 5 PAGE 72**

STATE OF MICHIGAN
 ST. JOSEPH COUNTY
 FILED

11 JUN 1998 9:52:35 AM

CYNTHIA L. JARRATT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION
 For corners in

ST. JOSEPH
 (County)

MOTTVILLE TWP.
 1. Public Land Survey

Located In:	T <u>8S</u> R <u>12W</u>	Corner Code #	<u>J-5</u>
	T <u> </u> R <u> </u>		<u> </u>
	T <u> </u> R <u> </u>		<u> </u>
	T <u> </u> R <u> </u>		<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>		<u> </u>
	S <u> </u> T <u> </u> R <u> </u>		<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>		<u> </u>
	S <u> </u> T <u> </u> R <u> </u>		<u> </u>

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, WAYNE A. MOSTROM, in a field survey on 4/30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5										⊙			
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>GLO</u>	<u>ROAD COMM. 1972</u>	<u>1977 SAYERS SURVEY</u>
<u>POST</u>	<u>FOUND ORIGINAL STAKE</u>	<u>SAME WIT. AS ROAD COMM.</u>
13" Y.O. = S69°E 2.22 CH.	40" WILLOW = N. 13.61'	<u>1984 LCRC IN 2/176</u>
15" Y.O. = N39°E 2.53 CH.	6" ASH = NE 29.85'	<u>½" CAPPED IRON #7874</u>
	12" WILLOW = SW 59.1'	6" ASH = NE 29.85' (DEAD)
	<u>1974 LCRC IN 1974</u>	10" TRI-MAPLE = SW 46.1'
	<u>SAME WIT.'S AS ABOVE</u>	4" MAPLE = SW 21.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CAPPED RANGE ROD SECTION DRIVEN THROUGH OLD STAKE 6" DEEP IN WATER
 12" WILLOW = SW 59.1'
 10" TRI-MAPLE = SOUTH 46.1'
 4" MAPLE = SW 21.6'

RATIFIED BY PEER GROUP
 IN ACCORDANCE WITH P.A. 345
 ON MAY 11, 1998
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 48" BAR W/STD. CAP THROUGH REMAINS OF OLD STAKE
 N & W IN S. SIDE 10" ELM = S72°E 25.50'
 N & W IN SW SIDE 10" MAPLE = S50°E 35.34'
 N & W IN E. SIDE 18" TRI-MAPLE - SOUTH 46.1'
 N & W IN SE SIDE 11" MAPLE = S32°W 21.60'
 N & W IN S. SIDE 16" QUAD-MAPLE = N54°W 27.30'



LIBER 5 PAGE 72

Signed by Wayne A. Mostrom
 Surveyor's Michigan License No. 14100

Date MAY 12, 1998