

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40 N.R. 17-18 W


Schoolcraft & Delta COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19, 24, 25, 30

CORNER MONUMENT 2" Iron Pipe with 2" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 1/27/61 with W. Wallace and Art Enger

WITNESSES TO CORNER....9" Cedar (S 19 NBT) N 70° E 15 Links



9" Cedar (S 30 NBT) S 14° E 35 Links

8" Cedar (S 25 NBT) S 40° W 33 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Tamarack B.T. bearing N 72° W, 41 Links. Tree has been cut. Found face with scribe marks in excellent condition. Several old blazes in vicinity.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE July 21, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler