

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40 N.R. 17 & 18


Schoolcraft & Delta COUNTY^S

DESCRIPTION OF CORNER Township Corner for Sections 1, T40N, R18W and Section 6, T40N, R17W on 4th Correction Line.

CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 7-11-61

WITNESSES TO CORNER..... 24" Hemlock (NBT) S 15°W 57½ links



9" Hemlock (S1 NBT) S 11°W 50 links

18" Y. Birch (NBT) S 01°E 40 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed 3.00 chains West of $\frac{1}{4}$ Corner on South side of Section 32, T41N, R17W as recorded in Field Notes. ($\frac{1}{4}$ Corner is original corner set by Carl Christensen).

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE January 31, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler