

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Schoolcraft Co.

Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 41 N. R. 13 E. W.	E-2
2. PROPERTY CONTROLLING IN SECTION 5 _____	T. 41 N. R. 13 E. W.	Meander Corner, 264.0' West of D-1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 5/14/1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
 E-2 1/2 Cor. bet. Secs. 4-5, set by John Mullett, D.S. in 1845.  
 Bearings were:  
 Aspen 10" S62°E 7 lks. and Spruce 7" S55°W 9 lks.

Meander Corner Set by John Mullett, D.S. 1845.  
 264.0' West of D-1 Witness was a W. Ash 12" N38°E 18 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 E-2 Re-established corner, in line with a row of pine trees to south. These trees were planted on line by a former land-owner.

N.C. Re-established on line and by record distance from 1/2 Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 E-2 1" pipe with 4" Brass cap at corner.  
 New Bearings:  
 5" W. Birch N29°E 2.4' and 6" W. Birch N70°W 29.2'  
 1" iron pipe N13°E 39.9'

N.C. Placed 1" pipe with 4" aluminium cap at corner.  
 No new witnesses.  
 Corner lies 264.0' West of 1/2 Cor. Northside, Sec. 5.

SIGNED BY Billy D. Buckler DATE 6/27/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_