

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

JAN 25 2000

DATE 12/15/99 *TOP*

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION _____

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

SIGRID HEDBERG

1P

SCHOOLCRAFT CO. REGISTER

Page 1 of 1

LC 4/315

JLO Date 12/30/1999

Time 13:54:10

RECORDING FEES:

9.00

1. Public Land Survey

T	41N	R14W	M4
T	41N	R13W	A4
T		R	
T		R	
S	T	R	
S	T	R	
S	T	R	
S	T	R	

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 12/29, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	X
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1845 John Burt, DS set qr. section post Y.Pine 7 N36E 2 Do. S48W 38

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec.29, 1999 Thomas P. O'Brien, PS reestablished corner by single proportionate measurement between M3 and M5. Set Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument

Witnesses:

4" Red Pine N48°W 35.55'

10" Red Pine N8°E 37.8'

12" Red Pine S26°W 23.95'

4" White Pine S26°E 18.03'

Carsonite Post North 1.0'



Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date Dec. 30, 1999

Surveyor's Michigan License No. 21274