

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

JAN 25 2000

DATE 12/15/99

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION \_\_\_\_\_

For corners in

Schoolcraft  
(County)

Located In:

Corner Code #

- |                                    |                             |       |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey              | T <u>41</u> N R <u>14</u> W | D3    |
|                                    | T ___ R ___                 | _____ |
|                                    | T ___ R ___                 | _____ |
|                                    | T ___ R ___                 | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___           | _____ |
|                                    | S ___ T ___ R ___           | _____ |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___           | _____ |
|                                    | S ___ T ___ R ___           | _____ |

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/321  
JLQ Date 12/30/1999 Time 13:55:57  
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on 12/28, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3				X									
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Sept. 6, 1845 John Burt, DS set qr. section post W. Birch 8 S41W 4 Y. Birch 15 N81E 28

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 28, 1999 Thomas P. O'Brien, PS reestablished corner by single proportionate measurement between C3 and E3. Set Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument

Witnesses:

- 14" Hemlock N14°W 10.02'
- 18" Hemlock S45°W 16.33'
- 20" Hemlock S18°E 18.50'
- 12" Hemlock S68°E 13.30'
- Carsonite Post North 1.0'



*Thomas P. O'Brien*

Signed by Thomas P. O'Brien

Date Dec. 30, 1999

Surveyor's Michigan License No. 21274