

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

JAN 25 2000

SECTION

DATE 12/15/99 508 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T41N R14W T42N R14W T___ R___ T___ R___	E1 ✓ E13 _____ _____
2. Property Controlling in Section	S___ T___ R___ S___ T___ R___	_____ _____
3. Miscellaneous Property in Sec.	S___ T___ R___ S___ T___ R___	_____ _____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/341
JLO Date 12/30/1999 Time 13:59:49
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 12/20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

April 1851 Algernon Merryweather, DS remeasured line and established corner
Y.Birch 12 N35E 6 Cedar 7 N32W 29

April 28, 1989 Gary E. Koepke, PS "Found old iron pipe, 1 1/2" I.D. 13/4" O.D. at intersection of fence line remains running North-South & West, and opposite face blaze in dead Pine, N55°E 35.4' to center of tree. Found pipe 2652.97 South of 1/4 Cor. Accepted found pipe as Section corner."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec.20, 1999 Thomas P. O'Brien, PS found 1" pipe at fence intersection. Existing witnesses verify corner position. Reset pipe with Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument
Witnesses:
5" Spruce North 7.13'
Centerline Dead Pine w/face blaze N55°E 35.4'
7" Balsam N60°E 9.22'
6" Balsam S75°E 5.52'
7" Spruce S80°W 10.77'
Carsonite Post North 1.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec.22, 1999