

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 12/15/99 ^{JOB} LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 25 2000

SECTION

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>41</u> N R <u>14</u> W | F3 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling
in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous
Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/324
JLO Date 12/30/1999 Time 13:56:46
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 12/27, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3						X							
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Sept. 6, 1845 John Burt, DS set qr. section post Maple 3 N61E 4 Hemlock 7 S55W 11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 27, 1999 Thomas P. O'Brien, PS reestablished corner by single proportionate measurement between E3 and G3. Set Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument

Witnesses:

8" Cedar N28°W 67.43'

4" Cedar S51°W 17.07'

4" Cedar S29°E 59.23'

10" Twin Maple N44°E 22.82'

Carsonite Post North 1.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date Dec. 30, 1999

Surveyor's Michigan License No. 21274

