

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

JAN 25 2000

SECTION

DATE 12/15/99 0015 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>14W</u>	G3
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/333
JLV Date 12/30/1999 Time 13:58:20
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on 12/21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3						X							
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Sept. 6, 1845 J. Burt, DS set post corner of Sections 3, 4, 9 & 10
Spruce 4 S74W 11 Do N63½E 40

Sept. 1, 1983 Thomas P. O'Brien, PS reestablished corner using recorded distance ties of Michibay Subdivision. Set iron bar w/21274 cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DEc. 21, 1999 Thomas P. O'Brien, PS recovered iron bar w/21274 cap at record plat dimension. Reset iron bar with Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument

Witnesses:

12" Maple N37°E 11.0'

6" White Pine N20°W 29.0'

6" Maple N70°W 8.02'

6" Maple S37°E 19.37'

Carsonite Post North 1.0'



Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date Dec. 22, 1999

Surveyor's Michigan License No. 21274