

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

JAN 25 2000

SECTION

DATE 12/15/99 JB LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>14W</u>	<u>J3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/335
JLV Date 12/30/1999 Time 13:58:41
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 12/18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3										*			
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Sept.5, 1845 J. Burt, Ds set qr. section post W.Pine 10 S31W 6 do 18 N½W 59

April 8, 1976 Thomas P. O'Brien, PS "set by single proportion between I3 and K3."

1979 Schoolcraft County surveyor reset iron bar with Schoolcraft County monument stamped to identify.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec.18, 1999 Thomas P. O'Brien found Schoolcraft County monument. Existing witnesses verify corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument

Witnesses:

- 12" White Pine N20°W 4.1'
- 16" White Pine S53°W 51.3'
- 6" Red Pine S13°E 32.65'
- 10" White Pine N87°E 17.40'
- Crasonite Post North 1.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec.22, 1999