

# SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 12/15/99 JOB LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 25 2000

SECTION

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>14W</u>	<u>K4</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/337  
JLV Date 12/30/1999 Time 13:59:08  
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on 12/18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11	X	12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Sept. 5, 1845 J. Burt, DS set qr. sec. post W. Pine 4 S43E 11 do 12 N23W 50

Oct. 28, 1939 M.S. McNabb, Reg. Surveyor refers to Quarter corner between Sections 11 & 12 in description of "OLD Deerfield Michigan Shores Addition"

April 9, 1990 Thomas P. O'Brien, PS "found post with bolt as set by Marcus McNabb, replaced bolt with a Schoolcraft County monument stamped to identify."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DEc. 18, 1999 Thomas P. O'Brien, PS found Schoolcraft County monument. Existing witnesses verify corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument  
Witnesses:  
14" Red Pine N21°E 28.55'  
10" Red Pine N61°W 27.50'  
8" Red Pine S39°W 16.90'  
10" White Pine N72°E 5.35'  
Carsonite Post North 1.0'



Signed by Thomas P. O'Brien

Date DEc. 22, 1999

Surveyor's Michigan License No. 21274