

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 12/15/1999 ^{JB}

JAN 25 2000

LAND-GORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION _____

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 41N R 14W	M3 ✓
	T 41N R 13W	A3
2. Property Controlling in Section	T ___ R ___	___
	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/328
JLO Date 12/30/1999 Time 13:57:32
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 12/23, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1845 John Burt, DS set post corner of sections 1 and 12
Y Pine 5 N65W 41 Do 15 S46W 30

Jan.15, 1957 Billy D. Buckler, RLS recovered 1" iron pipe with 4" brass cap as set by Carl Christianson, Manistique from Y Pine BT in place in fair condition. Added witnesses to corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec.23, 1999 Thomas P. O'Brien, PS recovered 1" iron pipe with 4" brass cap as set by Carl Christianson, Manistique. BT stump w/washer N65W 41 present. Added witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" Pipe with 4" brass cap
Witnesses:
Red Pine N83°W 51.48'
Red Pine N11°E 12.21'
6" White Pine S55°E 11.15'
4" Red Pine S26°W 18.60'
Carsonite Post North 1.0'



Signed by Thomas P. O'Brien

Date Dec.30, 1999

Surveyor's Michigan License No. 21274