

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 12/15/99

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 25 2000

SECTION

For corners in
Schoolcraft
(County)

Located In:	Corner Code #
T 41N R 14W	M4 ✓
T 41N R 13W	A4
T R	
T R	
S T R	
S T R	
S T R	
S T R	

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1
JLO Date 12/30/1999 LC 4/315
RECORDING FEES: Time 13:54:10
9.00

Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.
- Lot No. _____, Recorded Plat _____
- Private Claims _____

I, Thomas P. O'Brien, in a field survey on 12/29, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
1845 John Burt, DS set qr. section post Y.Pine 7 N36E 2 Do. S48W 38

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Dec.29, 1999 Thomas P. O'Brien, PS reestablished corner by single proportionate measurement between M3 and M5. Set Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Schoolcraft County monument

- Witnesses:
- 4" Red Pine N48°W 35.55'
 - 10" Red Pine N8°E 37.8'
 - 12" Red Pine S26°W 23.95'
 - 4" White Pine S26°E 18.03'
 - Carsonite Post North 1.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 30, 1999