

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Schoolcraft Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 16 X. W.	D-8
2. PROPERTY CONTROLLING IN SECTION 20	T. 41 N. R. 16 X. W.	8
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3-18, 19 82, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 8 Center of Section 20. Not prev. est.
West 1/16 cor. of section 20 on the E-W 1/4 line. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 8 Set at the intersection of the N-S and E-W 1/4 lines of sec. 20 by closed traverse.
Set M.F.C.L. between the center of section and the W 1/4 cor. of section 20.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|----------------------------|--------------------------|
| -8 D.N.R. Monu. Bearings: | 8 D.N.R. Monu. Bearings: |
| 12" Cedar, N8°E, 29.1' | 4" Cedar, S52°W, 31.5' |
| 12" W. Birch, N84°E, 29.9' | 5" Cedar, S70°E, 25.1' |
| 7" Cedar, S26°E, 17.1' | 4" Cedar, S54°E, 28.5' |
| 6" Cedar, S30°W, 25.2' | 6" Cedar, N81°E, 25.9' |

SIGNED BY

David E. Babbitt
David E. Babbitt

DATE 4-19-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: