

JAN 21 1999

SECTION

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 10/21/98 JOB

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

JAN 21 1999

SECTION

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T41NR16W	<u>A-4</u>
	T41NR17W	M-4
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/209
JLV Rec. Date 12/03/98 Time 14:26
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on Oct. 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4	X	7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A4 W 1/4 corner section 7, T41N - R16W
July 29, 1845 - John Burt D.S. set qr. section post common to sections 7 T41N - R16W and section 12 T41N - R17W, referenced by: Aspen 10 S40W 34 Sugar 4 N60W 5.

July 30, 1981 - Thomas P. O'Brien P.S. recorded an LCRC (L.1, Pg. 265 P.S. 21274) which indicates " Re-set from existing monumentation of plat of Hiawatha Shores Subdivision".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A4 Oct. 22, 1998 - Thomas P. O'Brien P.S. recovered a Schoolcraft County Monument stamped to identify. BT's recovered verify corner location as set on July 30, 1981.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A4 Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- (Fd.) 12" W.Pine - S20°W - 35.0'
- (Fd.) 14" W.Pine - N62°W - 41.70'
- NBT 10" Maple - N64°E - 149.28'
- SW Corner of house (brick front) S53°E - 172.02'
- Centerline Co. Rd. 455 - East - 52.75'
- Carsonite post - West - 2.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date November 29, 1998

Surveyor's Michigan License No. 21274

