

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

SURVEY &
REMONUMENTATION

JAN 21 1999

DATE 10/21/98 JOB

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T41N R16W	<u>A-7</u> ✓
	T41N R17W	<u>M-7</u>
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/ 212
JLV Rec. Date 12/03/98 Time 14:27
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Oct. 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


A7 NW Corner Section 19, T41N - R16W
July 29, 1845 - John Burt D.S. set post corner of sections 18 & 19 T41N - R16W and sections 13 & 24, T41N - R17W referenced by: W.Pine 24 S25W 6, Hemlock 14 N39W 32, Hemlock 22 N55W 29, Hemlock 6 S40E 39.
April 11, 1995 - LCRC by Gerald W Carlson (L.4 Pg.167 p.S. 24589) indicates he "Found a 3 1/2" diameter aluminum Schoolcraft County Monument stamped to identify the corner".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A7 Oct. 23, 1998 - Thomas P. O'Brien P.S. recovered a Schoolcraft County Monument stamped to identify. Witnesses recovered verify corner location as found by Carlson April 11, 1995.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A7 Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and made measurements to the following references:
(Fd.) 5" Cedar - S25°E - 31.50'
(Fd.) 7" Maple - S35°W - 41.65'
(Fd.) 7" W.Pine - N78°E - 11.02'
(Fd.) 4" Cedar - N13°W - 42.12'
(Fd.) NW fence corner - S4°W - 44.50'
Carsonite post - South - 1.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date November 29, 1998