

JAN 21 1999

# SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 10/21/98 <sup>DOB</sup> LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION \_\_\_\_\_

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T41NR16W T41NR17W T___R___ T___R___	A-8 ✓ M-8 _____ _____
2. Property Controlling in Section	S___ T___ R___ S___ T___ R___	_____ _____ _____
3. Miscellaneous Property in Sec.	S___ T___ R___ S___ T___ R___	_____ _____ _____

SIGRID HEDBERG  
SCHOOLCRAFT CO. REGISTER 1P  
Page 1 of 1 LC 4/213  
JLO Rec. Date 12/03/98 Time 14:27  
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ . Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on Nov. 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A8 W 1/2 Corner Section 19, T41N - R16W  
July 29, 1845 - John Burt D.S. set qr. section post common to Section 19, T41N - R16W and Section 24, T41N - R17W, referenced by:  
W. Pine 24 S 54 W 64 Y. Pine 24 N 81 W 55

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A8 Nov. 25, 1998 - Thomas P. O'Brien P.S. reestablished corner by single proportionate measurement between A-7 and A-11. Set Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A8 Schoolcraft County Monument stamped to identify. Established the following references, BT's have been blazed, scribed, painted and tagged:

- NBT - 8" J. Pine - N37°E - 46.77'
- NBT - 6" Maple Clump - S50°E - 7.98'
- "X" in center bolt on West edge tower base - N10°W - 303.36'
- Bottom West corner of (High Voltage) sign frame on tower S35°W - 141.16'
- Carsonite post - East - 1.0'

Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date November 29, 1998

