

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 10/21/98 JOB

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft (County) Located In: Corner Code # 1. Public Land Survey T41N16W A-10 T41N17W M-10 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 LC 4/215 JLV Rec. Date 12/03/98 Time 14:28 REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

I, Thomas P. O'Brien in a field survey on Oct. 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Numbers 6-12, 18-24, 30-36 are present in the grid.

A. Description of original monument and accessories and/or subsequent restoration:

A10. W 1/4 Corner Section 30, T41N - R16W July 29, 1845 - John Burt D.S. set qr. section post, referenced by: Cedar 6 S44W 20 Hemlock 8 N44W 50

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A10 Oct. 26 1998 - Thomas P. O'Brien P.S. reestablished corner by single proportionate measurement between A-7 & A-11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A10 Schoolcraft County Monument stamped to identify. Established the following references which are blazed, scribed, painted and tagged:

- NBT 10" Maple - N22°W - 48.75' NBT 8" Maple - N53°E - 9.32' NBT 10" Maple - S27°E - 25.42' NBT 8" Maple - S53°W - 39.10' Carsonite post - North - 1.0'

Signature of Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date November 29, 1998

Surveyor's Michigan License No. 21274

