

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

SURVEY &
REMONUMENTATION

DATE 10/21/98 JOB LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 1999

For corners in

Schoolcraft Located In: Corner Code #
(County)

SECTION

1. Public Land Survey T41NR16W A-11 ✓
T41NR17W M-11
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/216
JLO Rec. Date 12/03/98 Time 14:28
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Oct. 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

All NW Corner Section 31, T41N - R16W
July 29, 1845 - John Burt D.S. set post corner common to sections 30 & 31 T41N - R16W and sections 25 and 36, T41N - R17W. Referenced by:
Y. Birch 12 S 72 W 15 Fir 5 N 62 W 26
July 1983 - William F. Bowman L.S. 28406 " Re-established corner by proportionate measure on line between A-7 & A-13, and set a 1/2" rebar & I.D.cap"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

All Oct. 26, 1998 - Thomas P. O'Brien P.S. recovered a 1/2" I.B. with cap #28406, found NBT's check well with Bowman L.C.R.C. (L.1 Pg.355 L.S.28406). Replaced I.B. with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- (Fd.) 6" Balsam - N50°E - 43.40'
- (Fd.) 10" Aspen - S35°E - 27.0' (Fair cond.)
- (Fd.) 8" Maple - S65°W - 24.60'
- NBT 4" Cedar - N3°W - 19.42'
- NBT 12" W.Pine - S2°W - 162.78'
- C/L East and West road - South - 48'
- Carsonite post - North - 1.0'

Signed by Thomas P. O'Brien

Date November 29, 1998

Surveyor's Michigan License No. 21274

