

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

SURVEY &
REMONUMENTATION

JAN 21 1999

DATE 10/21/98 JOB

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft (County)	Located in:	Corner Code #
1. Public Land Survey	T41NR16W	B-5
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/219
JLO Rec. Date 12/03/98 Time 14:30
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Thomas P. O'Brien in a field survey on Nov. 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5	X												
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B5 N $\frac{1}{4}$ Corner Section 18, T41N - R16W
Sept. 14, 1845 - John Burt D.S. set qr. section post referenced by:
Hemlock 24 S 2 E 1.39 Y. Birch 14 West 4.54

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B5 Nov. 25, 1998 - Thomas P. O'Brien P.S. reestablished corner at GLO distance and bearing from A5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B5 Schoolcraft County Monument stamped to identify. Established the following references which have been blazed, scribed, painted and tagged:

- NBT - 8" Maple - N56°W - 25.58'
- NBT - 16" Maple - N75°E - 13.16'
- NBT - 6" Maple - S 2°E - 31.55'
- NBT - 8" Maple - S 70°W - 15.74'
- Indian Lake - East - 125'±
- Carsonite post - North - 1.0'

Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date November 29, 1998

