

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
REMONUMENTATION**

DATE 10/21/98 JUB **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 1999

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>16W</u>	<u>B-9</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___	___
	S ___ T ___	___
3. Miscellaneous Property in Sec.	S ___ T ___	___
	S ___ T ___	___

SECTION

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/ 221
JLO Rec. Date 12/03/98 Time 14:30
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Oct. 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B9 N 1/4 Corner Section 30, T41N - R16W
Sept. 15, 1845 - John Burt D.S. set qr. section post referenced by:
W. Birch 3 S 39 W 17 Cherry 3 N 43 E 15
Sept. 26, 1912 - Ernest Weaver, County Surveyor set a hemlock stake from an original witness, W. Birch 3 S 39 W 17.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B9 Oct. 27, 1998 - Thomas P. O'Brien P.S. found no evidence of Ernest Weaver's record survey of Sept 26, 1912. Recovered old fence post broken off and below ground surface. Replaced post with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B9 Schoolcraft County Monument stamped to identify. Established the following references which are blazed, scribed, painted and tagged:

NBT 22" W. Pine - N48°E - 71.42'
NBT 14" W. Pine - S63°E - 111.48'
NBT 10" R. Pine - S39°W - 12.40'
NBT 6" Cherry - N74°W - 12.76'
Fence Post Corner - SE - .50'
Carsonite post - South - 1.0'

Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date November 27, 1998

