

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 10/21/98 JOB

SURVEY &
REMONUMENTATION

JAN 21 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| <u>Schoolcraft</u> (County) | Located In: | Corner Code # |
|---------------------------------------|-------------|---------------|
| 1. Public Land Survey | T41NR16W | B-11 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

SECTION

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/222
JLO Rec. Date 12/03/98 Time 14:31
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | X | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

(Thomas P. O'Brien in a field survey on Oct. 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B11N 1/2 Corner Section 31, T41N - R16W
Sept. 15, 1845 - John Burt D.S. Hemlock 7 qr. section corner
referenced by : Hemlock 7 S 43 E 9

July 1983 - LCRC by William F. Bowman (L.1 Pg.355 L.S. 28406) indicates he re-established corner by " proportionate measure on line between A-11 & C-11 and set a 1/2" rebar with I.D. cap".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B11 Oct. 26, 1998 - Thomas P. O'Brien P.S. recovered a 1/2" rebar with I.D. cap # 28406 and 2 remaining (Dead) BT's check with Bowman LCRC (L.1 Pg. 355 L.S. 28406). Replaced rebar with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B11 Schoolcraft County Monument stamped to identify. Established the following references which are blazed, scribed, painted and tagged:

NBT 10" Maple - N75°E - 99.64' (Fd.) 12" Aspen - S30°E - 64.30' - Dead
NBT 14" R.Pine - S51°E - 121.48' (Fd.) 12" Spruce - S3°E - 46.75' - Dead
NBT 8" Maple - S50°W - 79.03'
NBT 6" Maple - N70°W - 90.62'
Carsonite post - North - 1.0'
C/L East & West Gravel Road - South - 21.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date November 27, 1998

Surveyor's Michigan License No. 21274

