

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

SECTION

DATE 10/21/98 008 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|----------------|---------------|
| <u>Schoolcraft</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T41N R16W | C-9 |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| 2. Property Controlling in Section | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |
| 3. Miscellaneous Property in Sec. | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/ 226
JLO Rec. Date 12/03/98 Time 14:32
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Oct. 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | X | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

C9 NW Corner Section 29, T41N - R16W
Sept 15, 1845 - John Burt D.S. set post corner of sections 19, 20, 29 & 30
referenced by: Hemlock 12 N 55 W 40 Hemlock 10 S 50 E 15
Sept. 25, 1989 - LCRC by Neil E. Hill (Liber 2 Pg. 234 L.S. 27447)
indicates "found 1/2" pipe in monument box in location as shown on road plans".
June 21, 1991 - Thomas P. O'Brien P.S. " recovered iron pipe in monument
box 4' West of centerline of M-149". As noted in Liber 2: of surveys Pg. 10
P.S. 21274 .

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C9 Oct. 27, 1998 - Thomas P. O'Brien P.S. recovered 3/4" iron pipe in
monument box 4' West of centerline M-149. BT's recovered check with Hill
LCRC (L.2 Pg.234 L.S.27447).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C9 3/4" Iron Pipe in Monument Box 4' West of M-149 centerline. Repainted
blazes on NBT's and made measurements to the following references:
(Fd.) 14" Twin R. Pine - S50°E - 58.97'
(Fd.) 26" W. Pine - S80°W - 61.90'
(Fd.) 8" W. Birch - N70°E - 43.48'
NBT 8" Cedar - N45°W - 80.85'
NBT 5" R. Pine - N46°E - 70.54'
Carsonite post - East - 30.0'



Signed by Thomas P. O'Brien

Date November 23, 1998

Surveyor's Michigan License No. 21274