

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

SURVEY &
REMONUMENTATION
SURVEY &
REMONUMENTATION
JAN 21 1999

DATE 10/21/98 JOS LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T41NR16W	C-10
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1 LC 4/ 227
JLO Rec. Date 12/03/98 Time 14:40
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30	X	29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Thomas P. O'Brien in a field survey on Oct. 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C10 W 1/4 Corner Section 29, T41N - R16W
Sept. 15, 1845 - John Burt D.S. set qr. section post referenced by:
Sugar 12 N 63 W 9 Beech 12 N 63 E 17

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C10 Oct. 21, 1998 - Thomas P. O'Brien P.S. recovered a 3/4" iron pipe 3.8' below black top surface, top of pipe bent. Raised pipe with I.B. and O'Brien cap#21274, set Monument Box. Centerline of M-149 3.0' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C10 I. B. with O'Brien cap # 21274 over found 3/4" iron pipe, set Monument Box. Established the following references :

- Con. R/W Marker - N40°W - 46.47'
- Con. R/W Marker - N51°E - 47.88'
- NBT 6" W.Pine - S50°E - 138.96'
- NBT 10" R.Pine - S42°W - 56.97'
- Carsonite post - East - 30.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date November 23, 1998

