

JAN 21 1999

SECTION

SCHOOLCRAFT COUNTY
HEIR GROUP APPROVED
DATE 10/21/98

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T41N R16W	C-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1 LC 4/228
JLO Rec. Date 12/03/98 Time 14:41
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Oct. 26 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11			X										
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C11 NW Corner Section 32, T41N - R16W
Sept. 15, 1845 - John Burt D.S. set post corner of sections 29,30,31 & 32
referenced by: Cedar 10 N29E - 32 Cedar 7 S24W - 22

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C11 Oct. 26, 1998 - Thomas P. O'Brien P.S. recovered a 1/2" Iron Bar and bearing trees as set by Beryl M. Jones, L.S. 23514. Replaced Iron Bar with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C11 Schoolcraft County Monument stamped to identify. Established the following references which are blazed, scribed, painted and tagged:

- (Fd.) 8" Cedar - S35°W - 35.79'
- (Fd.) 8" Cedar - N48°W - 54.03'
- NBT 3" Cedar - N37°E - 61.0'
- NBT 6" Maple - S38°E - 50.48'
- Carsonite post - North - 25.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date November 19, 1998

