

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 10/21/98 JDB LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Table with columns: Schoolcraft (County), Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 LC 4/229 JLO Rec. Date 12/03/98 Time 14:41 REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

Thomas P. O'Brien in a field survey on Oct. 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and an 'X' in row 13, column C.

A. Description of original monument and accessories and/or subsequent restoration:

C13 SW Corner Section 32, T41N - R16W 1848 - John Burt D.S. set post corner of sections 31 & 32 referenced by: Hemlock 10 N 70 E 30 W.Pine 30 N 38 W 28 Dec. 1982 - L.C.R.C. by Thomas P. O'Brien (L.1 Pg. 296 P.S. 21274) indicates that a Schoolcraft County Monument was "Reset corner S38°E 28lks. from 30" White Pine stump".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C13 Oct. 28, 1998 - Thomas P. O'Brien P.S. recovered Schoolcraft County Monument stamped to identify. Witnesses found check with O'Brien LCRC (L.1 Pg.296 P.S. 21274).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C13 Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- (Fd.) 8" Maple - N54°W - 16.65'
(Fd.) 8" Maple - N4°E - 24.75'
(Fd.) 10" Maple - N65°E - 24.80'
NBT 22" Twin Maple - S75°E - 7.14'
(Fd.) N 1/4 Corner Section 1 - T40N -R17W, Schoolcraft County Monument East - 93.89'
Carsonite post - North - 1.0'

Signed by Thomas P. O'Brien Surveyor's Michigan License No. 21274

Date November 23, 1998

