

**SCHOOLCRAFT COUNTY**  
**PEER GROUP APPROVED**  
 DATE 12/2/98 <sup>JOB</sup>

SURVEY &  
 REMONUMENTATION

JAN 21 1999

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION \_\_\_\_\_

For corners in

Schoolcraft Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 41 N 16 W D9  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

SIGRID HEDBERG 1P  
 SCHOOLCRAFT CO. REGISTER  
 Page 1 of 1 LC 4/274  
 JLV Rec. Date 12/28/98 Time 15:29  
 REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9			X									
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Thomas P. O'Brien in a field survey on Dec. 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D9 N½ Corner Section 29, T41N - R16W  
 Sept. 15, 1845 - John Burt D.S. set qr. section post referenced by:  
 Tamarack 14 N45E 12 W. Pine 12 S 6 E 24  
 March 18 & 19, 1982 - LCRC (L.1 Pg. 287) by David B. Babbitt RLS 21558 indicates " Set by extending a line from the SW Section Corner of Section 20 across a conc. mon. for the West 1/16 cor. on the South Sec. line and double the distance between those two corner mons. as shown in the drawing of a survey by G.A. Shadko for the Thompson State Fish Hatchery dated 1946."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D9 Dec. 14, 1998 - Thomas P. O'Brien P.S. recovered 1" iron pipe with 4" aluminum DNR cap stamped to identify. Existing witnesses found verify corner location as set by Babbitt 3/18-19/82.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D9 1" iron pipe with 4" aluminum DNR cap stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- 6" Tamarack - N 6°W - 6.95'
- 8" Tamarack - N40°E - 21.10'
- 8" Tamarack - N77°E - 27.35'
- 8" Tamarack - S55°E - 20.30'
- Carsonite post - West - 1.0'



*Thomas P. O'Brien*

Signed by Thomas P. O'Brien  
 Surveyor's Michigan License No. 21274

Date December 18, 1998