

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

SURVEY &
REMONUMENTATION

JAN 21 1999

DATE 10/21/98 TOB

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION _____

For corners in

Schoolcraft
(County)

Located In:

Corner Code #

1. Public Land Survey

T 41 N 16 W

D-11

T ___ R ___

T ___ R ___

T ___ R ___

T ___ R ___

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___

T ___ R ___

3. Miscellaneous
Property in Sec.

S ___

T ___ R ___

S ___

T ___ R ___

S ___

T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1
JLO Rec. Date 12/03/98 LC 4/ 231
REVENUE FEES: Time 14:42
9.00

Register of Deeds Stamp & File Number

I, Thomas P. O'Brien in a field survey on Oct. 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D11 N 1/4 Corner Section 32, T41N - R16W

Sept. 15, 1845 - John Burt D.S. set Cedar 5 qr. section corner

referenced by: Cedar 5 N 85 W 15.

Aug. 1936 - C. M. Cade C.E. set monument as noted in a survey of

Thompson Fish Hatchery, Michigan Dept. of Conservation, Division of Fisheries.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

D11 Oct. 27, 1998 - Thomas P. O'Brien P.S. recovered a 4" Iron Pipe with brass cap, stamped State of Michigan rest of cap illegable.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

D11 4" Iron Pipe with brass cap stamped State of Michigan rest of cap illegable. Established the following references; BT's have been blazed scribed, painted and tagged.

NBT 12" Cedar - N48°E - 42.94'

NBT 8" Cedar - S69°W - 59.93'

NBT 4" Cedar - N 2°E - 45.70'

SW Corner of Westerly wall on Dam - S62°E - 106.83'

Carsonite post - East - 1.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274

Date November 23, 1998

