

JAN 21 1999

SCHOOLCRAFT COUNTY
PUBLIC LAND SURVEY
DATE 12/2/98 OBT

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft Located In: Corner Code #
(County)

- 1. Public Land Survey T41NR16W D-13
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/ 279
JLO Rec. Date 12/28/98 Time 15:30
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Thomas P. O'Brien in a field survey on Oct. 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13					X								

A. Description of original monument and accessories and/or subsequent restoration:

D13 S 1/4 Corner Section 32, T41N - R16W
1848 - John Burt D.S. set qr. section post referenced by:
Y. Birch 18 S 25 W 25 Y. Birch 17 S 15 E 24

Nov. 10, 1976 - Thomas P. O'Brien P.S. recovered 1/2" pipe with 2"x 2" hub @ E, W, & N fence corner.

Nov. 12, 1982 - Thomas P. O'Brien P.S. recovered 1/2" pipe and replaced pipe with Schoolcraft County Monument stamped to identify.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D13 Oct. 28, 1998 - Thomas P. O'Brien P.S. recovered a Schoolcraft County Monument stamped to identify. Existing witnesses verify corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D13 Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- (Fd.) 8" Cedar - S44°E - 26.40'
- (Fd.) 12" Maple - S86°W - 33.10'
- NBT 8" Maple - N75°W - 33.95'
- NBT 10" Y. Birch - N70°E - 3.0'
- Carsonite post - East - 1.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date December 15, 1998

Surveyor's Michigan License No. 21274

