

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE 10/21/98 JCS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

JAN 21 1999

SECTION

For corners in

<u>Schoolcraft</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T41NR16W	E-5
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1 LC 4/232
JLV Rec. Date 12/03/98 Time 14:42
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Thomas P. O'Brien in a field survey on Oct. 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5					X								
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E 5 NW Corner Section 16, T41N -R16W
Sept. 12, 1845 - John Burt D.S. set post corner of sections 8,9,16 & 17
referenced by: Hemlock 14 N 67½ W 4 Hemlock 10 S 67½ E 25
Aug. 13, 1974 - LCRC by Herbert L. Fluharty (L.1 Pg.45 RLS 18223)
indicates he recovered a " DNR Monument in E. shoulder of Rd."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

E5 Oct. 29, 1998 - Thomas P. O'Brien P.S. recovered a 3½" Iron Pipe with brass cap stamped State of Michigan, NE Corner Sec. 17 - T41N - R16W 1939. Witnesses found check with Fluharty LCRC (L.1 Pg. 45 RLS 18223).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E5 3½" Iron Pipe with brass cap stamped to identify. Repainted in blue, on NBT's and made measurements to the following references:

- (Fd.) 16" Oak - N70°E - 33.90'
- (Fd.) 16" Oak - S30°E - 30.48'
- (Fd.) 16" Hemlock - S88°W - 51.62' (recorded as Fir)
- NBT 6" Oak - N26°W - 74.62'
- Carsonite post - East - 10.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date November 23, 1998