

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
RECORDS**

DATE 10/21/98 JOB

JAN 21 1999

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

SECTION

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 41N R 16W	E-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1 LC 4/234
JLO Rec. Date 12/03/98 Time 14:43
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7					X								
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P. O'Brien in a field survey on Oct. 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E7 NW Corner Section 21, T41N - R16W
Sept. 13, 1845 - John Burt D.S. set post corner of sections 16, 17, 20 & 21
referenced by: Cedar 4 N 12 E 7 Tamarack 7 S 79 W 13

April 7, 1995 - LCRC by Gerald W. Carlson (L.4 Pg. RLS 24589)
indicates he "found a 3 1/2" O.D. pipe with 3 3/4" State of Michigan
brass cap, 0.15' high in good condition".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E7 Oct. 29, 1998 - Thomas P. O'Brien P.S. recovered a 3 1/2" iron pipe with
brass cap stamped State of Michigan SE Corner S 17 - T41N - R16W 1845-1939.
Witnesses found verify corner location as found by Gerald W. Carlson on
April 7, 1995.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


E7 3 1/2" iron pipe with brass cap stamped to identify. Repainted blazes
on NBT's and made measurements to the following references:

- (Fd.) 6" Cedar - N41°W - 9.70'
- (Fd.) 8" Cedar - N16°E - 16.19'
- (Fd.) 6" Cedar - N72°E - 6.71'
- (Fd.) 8" Cedar - S19°E - 16.11'
- Carsonite post - West - 1.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274



Date November 23, 1998