

# SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 12/2/98 JPB

SURVEY &  
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 1999

For corners in

Schoolcraft Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

SIGRID HEDBERG  
SCHOOLCRAFT CO. REGISTER 1P  
Page 1 of 1 SECTION 4/ 249  
JLO Rec. Date 12/15/98 Time 14:25  
REVENUE FEES: 9.00

- |                                       |              |       |
|---------------------------------------|--------------|-------|
| 1. Public Land Survey                 | T41NR16W     | E-8   |
|                                       | T___R___     | _____ |
|                                       | T___R___     | _____ |
|                                       | T___R___     | _____ |
| 2. Property Controlling<br>in Section | S___T___R___ | _____ |
|                                       | S___T___R___ | _____ |
| 3. Miscellaneous<br>Property in Sec.  | S___T___R___ | _____ |
|                                       | S___T___R___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on Nov. 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E8 W 1/4 Corner Section 21, T41N - R16W  
Sept. 13, 1845 - John Burt D.S. set qr. section post referenced by:  
Tamarack 6 S 88 E 13 Tamarack 5 N 19 W 7

May 25, 1950 - Carl Christensen County Surveyor set a 2" iron pipe with brass cap, from original BT's Tamarack 6 S 88 E 13, Tamarack 5 N 19 W 7.

Feb. 28, 1957 - L.C.R.C. by Billy D. Buckler (L.3 Pg. 189 RLS) indicates he recovered a 2" pipe with brass cap, and Tamarack B.T. bearing N19°W 7 links in excellent condition, has been cut 6' high.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E8 Nov. 11, 1998 - Thomas P. O'Brien P.S. recovered a 1 1/2" Iron Pipe with 2" collar and brass cap stamped 20 1/4 21 C.C., and Tamarack stub lying down and rotted bearing N19°W - 4.50', found existing Buckler B.T.'s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E8 1 1/2" iron pipe with 2" collar and brass cap stamped C.C. Repainted blazes on NBT's and made measurements to the following references:

- (Fd.) 8" Cedar - N83°E - 12.25'
- (Fd.) 8" Cedar - S45°W - 11.22'
- NBT 6" Cedar - N43°W - 5.66'
- NBT 10" Tamarack - N38°E - 15.90'



*Thomas P. O'Brien*

Signed by Thomas P. O'Brien P.S.

Date November 23, 1998

Surveyor's Michigan License No. 21274