

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 12/2/98 JOBS LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

Table with columns: Schoolcraft (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 JLO Rec. Date 12/15/98 Time 14:22 REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

Thomas P. O'Brien in a field survey on Dec. 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Contains numbers 6-36 and an 'X' in row 9, column E.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E9 NW Corner Section 28, T41N - R16W Sept. 13, 1845 - John Burt D.S. set post corner of sections 20,21,28&29 referenced by: Tamarack 10 S67W 46 Tamarack 7 N57E 45 May 25, 1950 - Carl Christensen, County Surveyor set 4' x 2" iron pipe with brass cap stamped C.C. from original B.T. Tamarack 7" N57°W 45 links. February 28, 1957 - LCRC (L.3 Pg.188) by Billy D. Buckler RLS indicates "Fd. 2" iron pipe with brass cap, Tamarack BT bears N57°W 45 links in good cond. cut high. (Govt. notes has this BT as N57°E 45 links)."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

E9 Dec. 10, 1998 - Thomas P. O'Brien P.S. recovered 2" iron pipe with brass cap stamped C.C. Witnesses found verify corner location as found by Buckler 2/28/57.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

E9 2" iron pipe with brass cap stamped C.C. Repainted blazes on NBT's and established the following references which have been blazed, scribed, painted and tagged:

- 8" Cedar - N88°W - 12.45'
12" W. Pine - N3°W - 20.85'
6" Tamarack - S54°E - 7.93'
8" Cedar - S40°W - 31.31'
Carsonite post - North - 1.0'

Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274



December 14, 1998