

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

SURVEY &
REMONUMENTATION

JAN 21 1999

DATE 12/2/98 ^{JOB} LAND CORNER RECORDATION CERTIFICATE

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 41N R 16W	E 10
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/242
JLO Rec. Date 12/15/98 Time 14:23
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29	X	28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P. O'Brien in a field survey on Dec. 10, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E 10 W $\frac{1}{4}$ Corner Section 28, T41N - R16W
Sept. 13, 1845 - John Burt D.S. set qr. section post referenced by:
W. Pine 7 N42E 7 Cedar 6 S33 $\frac{1}{2}$ W 10
May 1978 - LCRC (L.1 Pg.203) by Thomas P. O'Brien P.S. indicates
" set iron bar and cap by proportionate measure".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E 10 Dec. 10, 1998 - Thomas P. O'Brien P.S. recovered iron bar with O'Brien 21274 cap. Witnesses found verify corner location as set on 5/78.
Reset iron bar with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E 10 Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and established the following references which have been blazed, scribed, painted and tagged:

- 8" Cedar - S25°E - 8.46'
- 6" Cedar - N55°E - 16.62'
- 8" Cedar - S32°W - 8.95'
- 6" Cedar - S74°W - 4.62'
- Carsonite post - North - 1.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274

Date December 2, 1998

