

JAN 21 1999

SECTION

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 12/2/98 JLB

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft (County)

Located In:

Corner Code #

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 JLV Rec. Date 12/15/98 Time 14:26 REVENUE FEES: 9.00

1. Public Land Survey

T41N R16W F5

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

I, Thomas P. O'Brien in a field survey on Oct. 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and an 'X' in row 5, column F.

A. Description of original monument and accessories and/or subsequent restoration:

F5 N 1/4 Corner Section 16, T41N - R16W Sept. 12, 1845 - John Burt D.S. set qr. section post referenced by: W. Birch 5 S 21 W 9 W. Pine 4 N 14 W 21 April 7, 1995 - LCRC (L. 4 Pg. 170) by Gerald W. Carlson P.S. 24589 indicates " Found an aluminum Schoolcraft County Survey Monument with a 3 1/4" cap stamped to identify, 0.25' high in good condition. Also found 1 1/2" I.D. pipe with smashed top, 2.1' high.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F5 Oct. 29, 1998 - Thomas P. O'Brien P.S recovered Schoolcraft County Monument stamped to identify. Existing B.T.'s recovered verify corner location as found by Carlson April 7, 1995.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F5 Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- (Fd.) 10" R. Pine - N26°W - 14.93'
(Fd.) 6" Cedar - N64°E - 9.85'
(Fd.) 9" Cedar - S15°W - 16.14'
NBT 6" Cedar - S42°E - 11.54'
(Fd.) 9" W. Pine - N74°W - 24.01' (Blown down)
Carsonite post - North - 1.0'

Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274

Date December 6, 1998

