

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 12/2/98 LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Table with columns: Schoolcraft (County), Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 LC 4/243 JLO Rec. Date 12/15/98 Time 14:23 REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Thomas P. O'Brien in a field survey on Dec. 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Contains numerical data points for survey locations.

A. Description of original monument and accessories and/or subsequent restoration:

F9 N 1/2 Corner Section 28, T41N - R16W Sept. 13, 1845 - John Burt D.S. set qr. section post referenced by: Tamarack 6 S70W 29 Tamarack 5 N32E 16 May 1978 - Thomas P. O'Brien P.S. recorded LCRC (L.1 Pg.203) " set iron bar and cap from original bearing tree tamarack 5", N32E, 16."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F9 Dec. 10, 1998 - Thomas P. O'Brien P.S. recovered iron pipe and O'Brien 21274 cap. Existing witnesses verify corner location. Reset iron pipe with Schoolcraft County Monument stamped to identify.

SURVEY & REMONUMENTATION

MAR 03 1999

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F9 Schoolcraft County Monument stamped to identify. Established the following references which have been blazed, scribed, painted and tagged:

- 6" Cedar - N44°E - 32.05'
6" Cedar - S57°E - 37.03'
6" Cedar - S17°W - 38.04'
8" Cedar - N59°W - 44.26'
20" W. Pine stump - S45°E - 39.20' (cut stump, bottom blaze & nail still good.)
Carsonite post - North - 1.0'

Signed by Thomas P. O'Brien

Date December 14, 1998

Surveyor's Michigan License No. 21274

