

JAN 21 1999

SECTION

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED  
DATE 12/2/98 JOB

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T41N R16W	G2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SIGRID HEDBERG  
SCHOOLCRAFT CO. REGISTER 1F  
Page 1 of 1 LC 4/270  
JLO Rec. Date 12/28/98 Time 15:28  
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on Dec. 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4	X	3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G2 W 1/4 Corner Section 3, T41N - R16W  
Sept. 12, 1845 - John Burt D.S. set qr. section post referenced by:  
Tamarack 3 S 42 E 10 Tamarack 6 N 70 E 12

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G2 Dec. 18, 1998 - Thomas P. O'Brien P.S. recovered 2" x 2.5' iron pipe. Distance to G3 checks well with GLO. Replaced iron pipe with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G2 Schoolcraft County Monument stamped to identify. Established the following references which have been blazed, scribed, painted and tagged:

- 8" Cedar - N 10° W - 10.32'
- 8" Cedar - S 77° E - 34.90'
- 6" Cedar - S 6° E - 26.26'
- 10" Cedar - N 71° W - 10.94'
- Carsonite post - North 1.0'

*Thomas P. O'Brien*

Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274

Date December 2, 1998

