

JAN 21 1999

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

SECTION

DATE 12/2/98 JOB LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft
(County)

Located In:

Corner Code #

1. Public Land Survey

T41NR16W

G4

T R

T R

T R

T R

2. Property Controlling
in Section

S T

T R

3. Miscellaneous
Property in Sec.

S T

T R

S T

T R

S T

T R

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1
JLO Rec. Date 12/28/98 LC 4/268
REVENUE FEES: Time 15:27
9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Dec 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9	X	10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G4 W 1/4 Corner Section 10, T41N - R16W
Sept. 11, 1845 - John Burt D.S. set gr. section post referenced by:
W. Pine 3 N 58 1/2 E 17 Aspen 5 S 32 1/2 W 15

March, 1996 - James H. Moore, RLS 28423 indicates " Found a squared wood post on West edge of clear-cut. The position of this post checks well with the found center of section, found Northeast 1/16 corner and plat corner of Lake Haven Estates. I accepted the wood post as the best available evidence for the corner location."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G4 Dec. 18, 1998 - Thomas P. O'Brien P.S. recovered 5/8" x 30" rebar stamped 9/10 alongside squared wood post. Existing witnesses verify corner location as set by Moore RLS 28423 March, 1996. Replaced rebar with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G4 Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- 8" R.Pine - N8°E - 23.94'
- 14" Oak - N82°E - 27.21'
- 6" R.Pine - S36°W - 9.29'
- 6" W.Pine - N66°W - 6.63'
- Carsonite post - North - 1.0'



Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274

Date December 20, 1998