

JAN 21 1999

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED

SECTION

DATE 12/2/98 <sup>JTS</sup> LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T41NR16W	G5
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/ 271  
JLV Rec. Date 12/28/98 Time 15:28  
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on Dec. 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5							X						
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G5 NW Corner Section 15, T41N - R16W  
Sept. 12, 1845 - John Burt D.S. set post corner of sections  
9,10,15 & 16 referenced by : Cedar 6 S70W 33 Tamarack 6 N42½E 30

March, 1996 - James H. Moore P.S. 28423 reestablished corner  
using Shadko's measurements.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G5 Dec. 15, 1998 - Thomas P. O'Brien P.S. recovered 5/8" x 30"  
rebar with 2" stamped aluminum cap. Found existing witnesses verify  
corner location as set by Moore, March 1996. Replaced rebar with  
Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G5 Schoolcraft County Monument stamped to identify. Repainted  
blazes on NBT's and made measurements to the following references:

- 9" Hemlock - N4°E - 43.20'
- SW corner of house - S43½E - 42.82'
- 10" Cedar - S64°W - 82.74'
- 8" Cedar - N50°W - 25.01'
- Carsonite post - West - 1.0'



Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date December 16, 1998