

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
REMONUMENTATION**

JAN 21 1999

DATE 12/2/98 ^{JOB} **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T41NR16W	G6
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/ 272
JLO Rec. Date 12/28/98 Time 15:28
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Thomas P. O'Brien in a field survey on Dec. 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G6 W 1/4 Coner Section 15, T41N - R16W
Sept. 12, 1845 - John Burt D.S. set gr. section post referenced by:
Tamarack 10 S39W 15 Tamarack 6 N72E 18
May 25, 1950 - Carl Christensen County Surveyor set 4' x 2" iron pipe with brass cap stamped C.C. from Tamarack 10" S39°W 15 links.
Feb. 21, 1957 - LCRC (L.3 Pg.191) by Billy D. Buckler RLS indicates "Found one tamarack B.T. in place in poor condition. BT bears S37W 15 lks."
April 7, 1995 - LCRC (L.4 Pg. 171) by Gerald W. Carlson P.S. indicates "Found 2" pipe with 2" diameter brass cap."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G6 Dec. 15, 1998 - Thomas P. O'Brien P.S. recovered 2" iron pipe with brass cap stamped 16 / 15 C.C. Recovered rotted tamarack stump bearing S37°W - 9.90' also found rotted squared top and scribed post below surface and lying flat alongside pipe. Existing witnesses verify corner location as found by Carlson 4/7/95.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G6 4' x 2" iron pipe with brass cap stamped to identify. Repainted blazes and made measurements to the following references:

- 12" Cedar - N9°E - 12.35 (to nail)
- 10" Cedar - N77°W - 20.58' (to nail)
- 9" Tamarack - S79°E - 7.45'
- 8" Tamarack - S2°E - 19.48'
- Carsonite post - North - 1.0'



Signed by Thomas P. O'Brien

Date December 16, 1998

Surveyor's Michigan License No. 21274