

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED

DATE 12/2/98 <sup>JOB</sup> LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

JAN 21 1999

For corners in

Schoolcraft Located In: Corner Code #  
(County)

- |                                    |              |       |
|------------------------------------|--------------|-------|
| 1. Public Land Survey              | T41NR16W     | G9    |
|                                    | T___R___     | _____ |
|                                    | T___R___     | _____ |
|                                    | T___R___     | _____ |
| 2. Property Controlling in Section | S___T___R___ | _____ |
|                                    | S___T___R___ | _____ |
| 3. Miscellaneous Property in Sec.  | S___T___R___ | _____ |
|                                    | S___T___R___ | _____ |

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/252  
JLO Rec. Date 12/15/98 Time 14:27  
REVENUE FEES: 9.00

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Thomas P. O'Brien in a field survey on Dec. 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9						X						
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G9 NW Corner Section 27, T41N - R16W  
Sept. 12, 1845 - J. Burt D.S. set post corner of sections 21, 22, 27 & 28  
referenced by: W. Birch 6 N61W 22 W. Birch 8 S46E 10  
May 1978 - LCRC ( L.1 Pg. 203) by Thomas P. O'Brien P.S. indicates  
"set iron bar and cap from stumps of birch bearing trees."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G9 Dec. 10, 1998 - Thomas P. O'Brien P.S. recovered iron bar with O'Brien  
21274 cap. All previous witnesses have been cut or blown down. Record  
distances East and West verify corner position. Reset iron bar with  
Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G9 Schoolcraft County Monument stamped to identify. Established the  
following references which have been blazed, scribed, painted and tagged:  
8" Cedar - S35°E - 35.0'  
6" Maple - S21°W - 43.85'  
8" Maple - N21°W - 24.90'  
6" Cedar - N57°E - 3.45'  
Carsonite post - West - 1.0'

*Thomas P. O'Brien*

Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date December 14, 1998

