

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

DATE 12/2/98

For corners in

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 LC 4/ 280 JLO Rec. Date 01/04/99 Time 13:15 REVENUE FEES: 9.00

Table with columns: Schoolcraft (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, Thomas P. O'Brien a field survey on 12/28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and an asterisk in row 3, column H.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: H3 1/4 corner common to sections 3 and 10 Sept. 11, 1845 John Burt, DS set gr. section post Y.Pine 22 S61°E 42 Y.Pine 18 N30°W 65

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: H3 Dec. 28, 1998 Thomas P.O'Brien, PS reestablished corner by single proportionate measurement between G3 and I3. Set Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: H3 Schoolcraft County monument stamped to identify. Established the following references which have been blazed, scribed, painted and tagged. 6" W.Pine N74°E 48.42' 6" R.Pine S47°E 33.20' 6" W.Pine S40°W 9.40' 8" W.Pine N75°W 5.20' Carsonite post North 1.0'

Signed by Thomas P. O'Brien Surveyor's Michigan License No. 21274

Date 12/31/98

