

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 12/2/98 JAB

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 LC 4/282 JLO Rec. Date 01/04/99 Time 13:16 REVENUE FEES: 9.00

Table with columns: Located In, Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, Thomas P. O'Brien a field survey on 12/23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

H5 1/4 corner common to sections 10 and 15 Sept. 12, 1845 John Burt, DS set qr. section post Cedar 10 N3 1/2 E 6 Cedar 9 S54W 6

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H5 Dec. 23, 1998 Thomas P. O'Brien, PS reestablished corner by single proportionate measurement between G5 and I5. Set Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H5 Schoolcraft County monument stamped to identify. Established the following references which have been blazed, scribed, painted and tagged:

- 8" Cedar S81°E 134.22'
8" Cedar S50°E 118.0'
4" Cedar S83°W 41.52'
6" Cedar N42°W 72.78'
Carsonite Post West 1.0'

Signature of Thomas P. O'Brien

Signed by Thomas P. O'Brien Surveyor's Michigan License No. 21274

Date 12/31/98

